



NOTE:  
ALL STEAMER NOZZLES ON FIRE  
HYDRANTS SHALL FACE THE STREET.

NOTE:  
ALL FILL AREAS TO BE COMPACTED  
TO 95% STANDARD PROCTOR  
DENSITY. TEST RESULTS WILL BE  
FURNISHED TO THE FIELD ENGINEER  
PRIOR TO CONSTRUCTION.

SCALE: 1" = 40' HORIZ.  
1" = 4' VERT.

1295	FL=1316.84 EP=1321.51		STA. 10+00 MATCHLINE	
1300	FL=1317.76		STA. 9+52.69 20' RT 1-6" FIRE HYDRANT 1-8"X6" TEE 1-6" GATE VALVE & BOX 1-12" RISER (IF NEEDED) STA. 9+09.68 N.W. 22ND ST.= STA. 0+00 ANGUS CIRCLE	
1305	FL=1318.29			
1310	FL=1318.52		STA. 8+65.27 20.00' RT= STA. 0+20.00 ANGUS CIRCLE 1-8"X6" TEE	
1315	FL=1318.52			
1320	FL=1318.85 EP=1323.52		STA. 7+59.29 18.54' RT 1-8"X11 1/4" BEND	
1325	FL=1317.23 EP=1321.89			
1330	FL=1318.52		STA. 5+75.76 20.00' RT 1-8"X11 1/4" BEND	
1335	FL=1317.23 EP=1321.89		STA. 5+25.16 28.62' RT 1-8"X11 1/4" BEND	
1340	FL=1313.43 EP=1318.09		STA. 4+63.32 27.78' RT 1-8"X11 1/4" BEND STA. 4+46.09 27' RT 1-6" FIRE HYDRANT 1-8"X6" TEE 1-6" GATE VALVE & BOX 1-12" RISER (IF NEEDED)	
1345	FL=1312.55			
1350	FL=1311.32			
1355	FL=1310.84 EP=1314.69		STA. 0+63.04 27' RT. 1-8"X45" BEND STA. 0+53.04 27' RT. 1-8"X45" BEND STA. 0+45.04 27' RT. 1-8" GATE VALVE & BOX	
1360	FL=1310.03 EP=1315.69		STA. 0+43.14 27' RT 1-6" FIRE HYDRANT 1-8"X6" TEE 1-6" GATE VALVE & BOX 1-12" RISER (IF NEEDED)	
1365	FL=1310.03 EP=1314.69		STA. 0+40.00 27' RT END ROAD BORE STA. 0+30.00 27' RT 1-8"X45" BEND	
1370	FL=1309.53 EP=1314.19		STA. 0+17.00 27' RT. 1-8"X45" BEND	
1375	FL=1309.03 EP=1313.69		STA. 0-14.00 27' RT BEGIN ROAD BORE STA. 0-17.00 27' RT 1-12"X8" TAPPING VALVE SLEEVE	
1380	FL=1308.84 FL=1305.90 FL=1305.90			
1385	FL=1308.91 FL=1308.95		STA. 0+00 CL OF HWY. 76	
1390				
1395				
1400				

WATER PLANS TO SERVE SUBURBAN ESTATES

**MORRIS**  
REGISTERED PROFESSIONAL ENGINEER  
ROSS C. MORRIS  
6837

617 N.W. 27th STREET  
MOORE, OK 73160  
(405) 912-2775  
(405) 912-2772 FAX  
CA 3549, EXP. 6-30-07

SCALE: HORIZ. 1" = 40' VERT. 1" = 4'

DATE: \_\_\_\_\_ ENGINEER

JOB NO. 4360 PROJECT NO. \_\_\_\_\_ SHEET NO. 4 OF 8